PHYSICAL TESTING REPORT





ACA (Kent) Ltd - T/A Spicer Tiles Mountfield House Mountfield Road **New Romney TN28 8LH**

FAO: Mr. Adam Spicer

Report of Tests on: Handmade Clay Roof Tiles

Your Reference: SPIPT01

Lucideon Reference: (181571)-13583

Date Reported: Order Number: 04-Apr-2018 **BACS**

Date(s) of Test(s): 03-Apr-2018 to 03-Apr-2018 21-Mar-2018 **Date Logged:**

Determination of Flexural Strength

BS EN 538: 1994: Clay Roofing Tiles for Discontinuous Laying


	Flexural Strength
No.	kN
1	0.77
2	0.92
3	0.89
4	0.73
5	1.06
6	0.95
7	0.93
8	0.94
9	1.05
10	0.96
Mean	0.92

Span: 177 mm

Does the sample comply with the BSEN1304: 2005 Clause 4.4.2? Yes

Opinions and interpretations expressed herein are outside the scope of UKAS Accreditation.

End of Test Report



Lucideon Limited

Stoke-on-Trent